


STARPATH

Starmine: An End-to-End Robotic System for Lunar Mining and LOX Production

Brian Yamauchi

Space Robotics Workshop 2025

Starpath Mission




Starmine Concept

- Starmine components
 - Rover drives into permanently shadowed regions and mines regolith
 - Plant converts water from regolith into liquid oxygen
 - Tower provides electricity from vertical solar array
- Lunar transport
 - Launches on Starship, Falcon 9, or New Glenn
 - Delivered by Starship, Griffin, or Blue Moon to Lunar South Pole
 - Lunar Terrain Vehicle places Plant and Tower for maximum solar exposure
 - Starmine designed to be carried on Astrolab FLEX LTV



Rover

- Four independently-steerable wheels with three drive modes
 - Drive forward/backwards using Ackermann steering
 - Strafe left/right using Ackermann steering
 - Rotate in place
- Active compliant suspension
- Two arms with barrel actuators to dig and gather regolith
- Articulated dump truck for depositing regolith at Plant




Rover Timeline

- Development started in 2022
- Rover 8
 - Won first place in 2023 NASA Break the Ice Challenge
 - Demonstrated continuous operation over 15 days
- Rover 9
 - Won second place in 2024 NASA Break the Ice Challenge
 - Demonstrated mobility over rough terrain simulating lunar surface
 - Demonstrated mining regolith simulant
- Rover 10
 - Currently in TVAC Testing at NASA Marshall Space Flight Center



Rover TVAC Testing

- Rover 10 currently being tested at NASA MSFC
- Simulated lunar conditions
 - 10^{-6} Torr vacuum
 - LN₂ cold shroud (-180° C)
 - Simulates mining in PSR for 12 hours
 - Heat lamps (1400 w/m²)
 - Simulates traveling at lunar noon for 12 hours
 - Mining pit filled with icy regolith simulant
 - 10° traversal slope covered in regolith simulant
- Integrated testing
 - Mobility
 - Mining
 - Charging
- Hardware testing
 - Actuators
 - Sensors
 - Avionics
 - Wheels
 - Excavation barrels
 - Charger
- Gathering data to calibrate thermal models




Rover Sensors

- RGB camera (Lucid Triton)
 - Teleoperation and visual odometry
- Time-of-flight camera (WASP, Lucid Helios)
 - Obstacle detection, mapping, LIDAR odometry
 - Working with Nat Gill at NASA GSFC on WASP time-of-flight camera for lunar environment
- IMU (VectorNav, MicroStrain)
 - Relative orientation
- Star tracker (Rocket Lab)
 - Absolute orientation
- Wheel encoders
 - Translation distance (but expect large amounts of wheel slip)
- Radio beacon direction finder (Kraken SDR)
 - For relative bearing to Plant/Tower




Rover Autonomy




Plant

- Converts regolith to rocket fuel
 - Auger system moves regolith through plant
 - Heats icy regolith to separate water as steam
 - Electrolyzes water into hydrogen and oxygen using proton-exchange membrane
 - Liquifies oxygen into LOX
- Production target
 - 60 metric tons of LOX per year per Plant



Integrated Test

- Rover delivered icy regolith to Plant
- Augers moved regolith through Plant processing mechanism
- Plant heated regolith and generated steam to distill water
- Icy regolith
 - Lunar highlands regolith simulant
 - Mixed with water
 - Cooled with liquid nitrogen



Regolith Desiccation and Water Distillation



Heated regolith moving through auger system



Steam refined from icy regolith

Tower

- Vertical solar array tower
 - Designed for highly illuminated regions at the Lunar South Pole
- 100 kW power generation capacity
- Yaw-axis tracking follows the Sun throughout illumination periods
- Solar banners retracted and heated to survive full-shade periods



10x speed



Deployable Composite Mast

- Being developed in collaboration with Atomic-6
- 45 m tall central mast
- Launches in compact roll
- Deploys on Moon



Site Selection and Traverse Planning

- Used terrain data to find peaks near Lunar South Pole with maximum sunlight exposure
- Identified PSRs that are likely to contain water
- Plan traverse to minimize distance and slope
- Traverse based on Moon Trek data
 - Mons Mouton PSR to nearby peak
 - 8x vertical scale
 - 15 km one-way



Next Steps

- Rover 11
 - Build hardware to meet flight requirements
 - Implement autonomy system
 - Test autonomous navigation in desert
- Plant 3
 - Build, test, and integrate water extraction, processing, and electrolysis systems
- Tower 2
 - Demonstrate deployable mast integrated with solar banners
- Goal
 - Full Starmine system ready for flight by 2027

